

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02762-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 27-13S-17W  
330 feet from S Section Line, 1140 feet from E Section Line  
Lease Name: DREILING B Well #: 6  
County: ELLIS Total Vertical Depth: 3525 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 47 MICHAWANIC ROAD #3D  
SANBORNVILLE, NH 03872

PROD Size: 4.5 feet: 3518 w/100 sxs cmt  
SURF Size: 8.625 feet: 176 w/130 sxs cmt

*# 114<sup>56</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STARR SCHLOBOHM Company: SCHLOBOHM, STARR F. Phone: (603) 522-9760

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Emergency plug with rig over the hole.  
Fish at 2600' - tubing and rods (750') - packer in the hole. Fluid level 100'.  
10-2001 - squeezed at 2700' w/220 sxs.  
10-2001 - squeezed at 890' - 981' w/150 sxs.  
11-2001 - squeezed at 2800' w/15 sxs.  
11-15-2001 - squeezed at 690' w/100 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2004 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dug out backside. Allied Cementing rigged to backside and pumped 5 sxs 60/40 pozmix.  
Max. P.S.I. 600#. S.I.P. 350#.  
RIH with tubing to 2500' - pumped 50 sxs neat followed with 60 sxs 60/40 pozmix with 350# hulls mixed in.  
Cement circulated to surface.  
Pulled tubing - tied onto 4 1/2" casing with a swedge.  
Pumped 25 sxs 60/40 pozmix with 50# hulls mixed in.  
Max. P.S.I. 1200#. S.I.P. 1000#.

Perfs:

Top	Bot	Thru	Comments
3516	3520		

RECEIVED  
AUG 12 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #15222.

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

*110*

INVOICED

DATE 8-12-04  
TEL. NO. 2005060348

AUG 10 2004

