

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22949-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 20-8S-22W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WHITE TRUST Well #: 1-20  
County: GRAHAM Total Vertical Depth: 3702 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: P.O. BOX 1469  
PLAINFIELD, IL 60544

PROD Size: 5.5 feet: 3686 110 SX CMT  
SURF Size: 8.625 feet: 206 160 SX CMT

*\$120<sup>32</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2004 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed  
Plugging  
Method:

Ordered 300 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 08/09/2004 2:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: ROGER MOSES

Actual Plugging Report:

Shot 5 1/2" casing off at 2820'.  
Pulled casing to 1858' - spotted 130 sxs cement with 300# hulls.  
Pulled casing to 1025' - spotted 40 sxs cement with 200# hulls.  
Pulled casing to 236' - circulated with 80 sxs cement.  
Pulled all casing and topped off well with 10 sxs cement.  
Total of 260 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3488	3492		

RECEIVED  
AUG 12 2004  
KCC WICHITA

Remarks: COPELAND ACID & CEMENT. SMOKY HILL TANK-WATER.

Plugged through: CSG

District: 04

*HO.*

Signed

*Roger & Moses*  
\_\_\_\_\_  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

*8-12-04*

TEL. NO.

*2005060347*

AUG 10 2004

RUSSELL OIL  
PLAINFIELD IL 60544

20-08S-22W  
SW SW NE

#1-20 WHITE TRUST

site 1 S & 2 E OF HILL CITY KS

cty: GRAHAM

API 15-065-22949

contr: SHIELDS DRILLING #1

field: HIGHLAND NORTH

geol:

tr  
date 11/25/2003

spd  
date 01/30/2004

drig  
comp 02/08/2004

card  
issued 05/31/2004

last  
revised 06/14/2004


ELV: 2184 GL LOG

tops	depth/datum
ANH	1788 +396
B/ANH	1822 +362
HEEB	3404 -1220
LANS	3443 -1259
STARK	3617 -1433
BKC	3654 -1470
PBTD	3671 -1487
RTD	3700 -1516
LTD	3702 -1518

IP status:

TEMP ABD, 03/05/2004

NOTE: INFO RELEASED 6/14/2004 - ADDED MISC INFO

CSG: 8-5/8" 206 / 160 SX (ALT 2), 5-1/2" 3686 / 110 SX

COMMENT: MI & RURT 1/30/2004

NO CORES

DSTS TAKEN - DETAILS NA

TRGT ZN: LKC (OIL), PTD 3700 (MARM), MICT - CO, PB

3671, PF (LKC) 3489-3492, W / 4 SPF, AC 500 GAL (15% MA)

& 1500 GAL (15% NE), TRACER SURVEY INDICATES

TRTMNT REMAINED IN ZN, SWB 20 BWP, W/TR OIL, SI -

EVAL FOR P & A, TEMP ABD (3/5/2004) - NO OTHER INFO

AVAILABLE - TEMP COMP 5/31/2004

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS