

To:
 STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

19523
 API NUMBER 15-121-90314-00-00
 NWNWSW Sec/Twp/Rge 18-17S-25E

2267 feet from south section line
 4839 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# SEABORN 7

Operator License # 101

County MIAMI

Operator: STATE OF KANSAS

Well Total Depth 430 feet

Name & FEE FUND

Production Pipe: 2 Size Feet 430

Address

Surface Casing: 8 Size Feet 20 EST

AB oil well Gas Well SWD Well/ Input Well E14695.12 D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS.66720

Company to plug at: Hour: Day: 23 Month: JUNE 2004

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-9212

Were: FILL WELL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All Part X None

Operations Completed: Hour: Day: 26 Month: JULY 2004

Actual Plugging Report: COULDN'T PULL 2". TWIST OFF WELL HEAD WITH BACKHOE.

CEMENT INSIDE 6 1/4". 2" CEMENTED IN. RUN 1" TO 430 FT. PULL 1" OUT AND RUN REAMER TO

BOTTOM. PULL OUT. PERFORATE WELL. RUN 1" TO 425 FT. CEMENT FLASHED. BACK OFF 1" AND

PULL 200 FT. SQUEEZED WITH CEMENT. TOOK NO MORE CEMENT. PUMP TOTAL OF 41 SACKS OF

PORTLAND CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER- 20040020-008 GPS # SEA 08
 (If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:


 Frank G. Guilfoyle
 TECHNICIAN

RECEIVED

AUG 12 2004

KCC WICHITA