

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20265-00-00
Spot: SW Sec/Twnshp/Rge: 17-29S-2E
1470 feet from S Section Line, 3960 feet from E Section Line
Lease Name: FARBER Well #: 1
County: SEDGWICK Total Vertical Depth: 3507 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3497 175 SX CMT
SURF Size: 8.625 feet: 130 100 SX CMT

\$ 113⁹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2004 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: SAND BACK TO 3457', DUMP BAIL 5 SX CMT OR SAND, SHOOT AND PULL 5-1/2", RUN PIPE INTO 180', CIRCULATE CEMENT TO SURFACE, PULL PIPE, TOP OFF WELL.
OPEN HOLE 3497'-3507' 10' TOP CEMENT 2700'.
RECEIVED
KCC DISTRICT #2
AUG 9 - 2004

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE WICHITA, KS
Date/Time Plugging Completed: 04/13/2004 5:00 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

SANDED FROM 3507', DUMP BAILED 5 SX CMT SHOT PIPE OFF @ 1725'; LAYED DWN PIPE, RUN TBG TO 180', CIRC CMT TO SURF. PULLED TBG, TOPPED OFF W/CMT 60/40 POZ, 4% GEL.

Perfs:

Top	Bot	Thru	Comments
3497	3507		

RECEIVED
AUG 06 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed David Wertz
(TECHNICIAN)

INVOICED
DATE 8-9-04
INV. NO. 2005060330