

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23163-00-01
Spot: E2E2NW Sec/Twnshp/Rge: 24-21S-12W
1320 feet from N Section Line, 2210 feet from W Section Line
Lease Name: WILSON TRUST OWWO Well #: 1-24
County: STAFFORD Total Vertical Depth: 3675 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 5.5 feet: 3663 WITH 150 SX CMT
SURF Size: 8.625 feet: 265 275 SX CMT

44
\$119

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2004 3:20 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3508' WITH 5 SX CMT. PLUG AT 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2004 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 3510'. SANDED TO 3508' WITH 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
3598	3612		
3585	3592		
3576	3582		
3564	3570		
3556	3560		

RECEIVED
AUG 09 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2020' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael J. Maier
(TECHNICIAN)

INVOICED
DATE 8.9.04
INV. NO. 2005060332

Form CR-28