

3-7-89

6 090409

API NUMBER 15- 137-20,370 -00-00

SW \_\_\_\_\_, SEC. 20, T 3, S, R 24 W/E

\_\_\_\_\_ 660 feet from S section line

\_\_\_\_\_ 3630 feet from E section line

Lease Name Clark Well # 1

County Norton 120.58

Well Total Depth 3710 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 249

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9121

Operator: Kiwanda Energy Inc.  
Name & Address: Box 1320  
Wichita, Ks. 67201-1320

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_ X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: 3 Month: Mar Year: 19 89

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone) \_\_\_\_\_

were: Order 205 sks 60/40 Poz 6% Gel and 8 5/8" wiper plug. Spot  
all plugs through drill pipe w/heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour 5:30AM Day: 7 Month: Mar Year: 19 89

- 1st plug 3655' w/20 sks
- 2nd plug 1925' w/20 sks
- 3rd plug 1235' w/100 sks
- 4th plug 300' w/40 sks
- 5th plug 40' w/wiper plug and 10 sks
- 15 sks in rathole

Remarks: Elevation 2335' Anhy 1909' Arb Yes. Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-16-89

INV. NO. 24122

3-7

Feb 9

Signed Edwin A. Schumacher (TECHNICIAN)

Edwin A. Schumacher

RECEIVED STATE CORPORATION COMMISSION MAR 4 1989 3-14-89 CONSERVATION DIVISION Wichita, Kansas