

✓ TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20416-00-00
Spot: NESESW Sec/Twnshp/Rge: 16-3S-24W
990 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WALLACE REYNOLDS Well Number: 1-16
County: NORTON Total Vertical Depth: 3660 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 232
Production: Size feet:
Liner: Size feet:

118.95

Well Type: DH UIC Docket No: Date/Time to Plug: 01/30/2001 8:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL WINN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 01/31/2001 12:15 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 1930' w/25 sxs. Middle of Anhydrite.
2nd. Plug at 1250' w/100 sxs. Dakota Base.
3rd. Plug at 280' w/40 sxs Base surface pipe.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 02-07-2001
INV. NO. 2001061424


RECEIVED
STATE CORPORATION COMMISSION
FEB - 5 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

HD