

15-137-00582-00-00

6 031544

API NUMBER 15- 1954

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE SE, SEC. 25, T 3 S, R 24 W4E

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Calvin Lawson Well # 3

Operator: Gore Oil Co.

County Norton 121.09

Name & Address Box 2757

Well Total Depth 3726 feet

Wichita, Ks. 67201-2757

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor b. J. Services License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 3 Month: May Year: 19 91

Plugging proposal received from Scott

(company name) Gore (phone)

were: 8 5/8 set at 242 w/125 sks. 5 1/2 set at 3724 w/100 sks. O.H. 3724 - 26.

Order 400 sks 65/35 poz 10% gel 400 lbs hulls. 13 sks gel. B. J. Services

Gore and Webb Water Trucks. Petrol Jet Logging.

Ran wireline to t.d. hole open. Shots at 2050 and 1275

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:10P Day: 3 Month: May Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 w/100 sks cement blend w/200 lbs. hulls.

Mixed in followed w/13 sks gel followed w/175 sks cement blend to max psi 750 lbs. Close in psi 550 lbs. Sq 8 5/8 w/100 sks cement blend w/200 lbs.

hulls mixed in to max psi 400 lbs. Close in psi 400 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

6-7-91 JUN 07 1991

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 6-17-91

INV. NO. 32154

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow