

To: 6 040886  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-12 158937-00512-00-00  
API NUMBER 15- 7-1954

SE SW SW, SEC. 25, T 3 S, R 24 W/2  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135  
Operator: John O. Farmer  
Name & Address Box 352  
Russell, Ks. 67665

Lease Name Schoen C Well # 1  
County Norton 122.56  
Well Total Depth 3771 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 280' w/125

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 12 Month: May Year: 19 88

Plugging proposal received from Lawrence Slim Eichman

(company name) John O. Farmer (phone) \_\_\_\_\_

were: 5 1/2" casing set at 3765' w/75 sks cement. Perfs at 3574' to 3688'.

Perf at 1350'. Ordered 250 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 175 sks cement w/1/4# F.C. plus 4 sks Hulls  
mixed in cement. Max Psi 900# Shut in 500#. Pumped in 8 5/8" casing 75 sks cement  
w/1/4# F.C. plus 1 sk Hulls. Max Psi 300# Shut in 150#.

RECEIVED  
STATE CORPORATION COMMISSION  
7-6-88  
JUL 6 1988

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I ( ) do hereby certify to observe this plugging.

DATE 7-7-88  
INV. NO. 21214

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis Hamel