

5-3 15-137-00142-00-00

88
R

6 031543

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1954

NE NE SE, SEC. 25, T. 3 S, R. 24 WE

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Calvin Lawson Well # 4

Operator: Gore Oil Co.

County Norton 120.41

Name & Address Box 2757

Well Total Depth 3705 feet

Wichita, Kansas 67201-2757

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.J. Services License Number -

Address Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 3 Month: 5 Year: 19 91

Plugging proposal received from Scott

(company name) Gore Oil Company (phone)

were: 8 5/8 set @ 224' w/125 sx. 5 1/2 set @ 3704' w/100 sx. O.H. 3704' -05'

Order 400 sx. 65/35 poz. 10% Gel. 500# Hulls, 13 sx. Gel. B.J. Services

Gore and Webb water trucks.

Ran wire line to T.D. hole open. Shots @ 2050' and 1275'

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2:25 P.M. Day: 3 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 5 1/2 w/100 sx. Cement Blend w/200# Hulls.

Mixed in followed w/13 sx. Gel. Followed w/175 sx. Cement Blend w/100# Hulls

mixed in to max. PSI 800#. Close in PSI 700#. Squeezed 8 5/8 w/100 sx. Cement

Blend w/200# Hulls mixed in to max PSI 200#. Close in PSI 200#. Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION
5-20-91

MAY 20 1991

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 5-29-91

WELL NO. 31938

Gib S.

Signed Carl Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas