

15-147-20006-00-01

4-27 4-032055

E 13,834-0002
~~E-08,461~~

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15- - 1967
W2 E2 SW /4 SEC. 31, 01 S, 18 W
1320 feet from S section line
3630 feet from E section line

Operator license# 5242 Lease Huffstutter well # C-3
Operator: P.M.I. County Phillips 119.15

Address: 14201 E. Central Well total depth 3666 feet
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 27 Month: April Year: 95

Plugging proposal received from: Don Keener

Company: P.M.I. Phone:

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Order work string.

Plugging Proposal Received by: Carl Goodrow - Don Butcher
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 27, Month: April, Year: 95

Actual plugging report: 8 5/8" set at 211' w/150 sxs. 4 1/2" set at 3665'
w/250 sxs. Prod. perfs. 3442' - 3594'. Critical area control shots at 1250'.
Ran tubing to 1700+ and mixed and pumped below tubing w/100 sxs. cement blend
to circulate. Pulled tubing. Squeezed 4 1/2" with total 140 sxs. cement
blend w/500# hulls to Max. P.S.I. 1200#. Close in P.S.I. 800#. Squeezed 8
5/8" with 100 sxs. cement blend to Max P.S.I. 500 Close in P.S.I. 150
Plug complete.

Remarks: DK top 1000+.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES 1824 NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2256 GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
STATE CORPORATION COMMISSION
(agent)
Form CP-2/3

INVOICED
DATE 5-18-95
INV. NO. 43855

MAY 15 1995
05-15-95
CONSERVATION DIVISION
WICHITA, KANSAS