

15-153-20062-00-01X 8-31
6 010634

API NUMBER 15- E-15,426
C NW, SEC. 8, T 1 S, R 33 W/E
_____ feet from S section line
_____ feet from E section line

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4074
Operator: Innes Pet Co. Inc.
Name & Address Morris Dr.
Phillipsburg, Ks.

Lease Name Palmer Well # C-3
County Rawlins 137.48
Well Total Depth 4,230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ Same _____ License Number _____

Address _____ Same _____

Company to plug at: Hour: 11:00AM Day: 31 Month: August Year: 19 88

Plugging proposal received from Rod Innes

(company name) Same (phone) _____

were: Order 50 sks Common Cement 200 sks ATL Cement 200 sks 60/40 Poz
8% Gel 400# Hulls. 4 1/2" casing at 4229'. Perf at 2180' and pulled
2 3/8" tubing. Squeezed at 925' w/250 sks and 3100' to 3300' w/350 sks.

Elev. 3029'

S.L.D. 1150' = 1879 = 2180' Plugging Proposal Received by _____
STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 31 Month: August Year: 19 88

ACTUAL PLUGGING REPORT

Pumped down casing 50 sks Common Cement. Then 150 sks ATL w/100# Hulls. Then, 100 sks
60/40 w/50# Hulls 700# max 200# close. Pumped down 8 5/8" 50 sks ATL and 100 sks 60/40 w/
250# Hulls. 400# max 200# close.

Remarks: Allied Cement Co.
(If additional description is necessary, use BACK of this form.)

INVOICED
(could) did not observe this plugging.

DATE 1-5-89
INV. NO. 23183

Signed Dale F. Balthazor
(TECHNICIAN)
Dale F. Balthazor

JAN 06 1989 JAN 25 1989