

4-041706 15-153-20057-00-01

8-14

D-22,203

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- -

NE NW SW NW /4 SEC. 08, 01 S, 33 W  
3880 feet from N section line  
4880 feet from E section line

Operator license# 4074

31274  
R.L. Horbek

Lease: Palmer 'C' Well # 2

Operator: Innes Petroleum, Inc.

County: Rawlings 92.95

Address: P.O. Box 25  
Phillipsburg, Kansas 67661

Well total depth P.B. 2860 feet

Conductor Pipe: 0 inch @ 0 feet

Surface pipe 8 5/8 Inch @ 299 feet

W/250 sxs.

Aband. Oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Oberlin, Kansas 67749

Company to plug at: Hour: 11:00 A.M. Day: 14 Month: August Year: 1995

Plugging proposal received from: Mike Van Ausdale

Company: Innes Petroleum, Inc. Phone:

Were: 4 1/2" casing set at 4209' with 250 sxs cement. Perf. At 2605' - 2690'. Squeeze at 1450' - 1700' with 250 sxs. Squeeze at 2178' with 75 sxs common plus 75 sxs posmix. Squeeze at 2841' with 125 sxs. Ordered 100 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1995

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:30 P.M., Day: 14, Month: August, Year: 1995

Actual plugging report: Tubing and packer stuck at 2425'. R.U. cementers to pump down tubing to plug bottom. Pumped 10 bbls cement slurry (70 sxs cement) with slight blow on annulus. Tubing loaded and pressured up to 800#. Opened annulus and continued pumping cement - circulated to surface with 27 total bbls of cement. Pumped (125 - 135 sxs). Prepare to back-off tubing: Backed off tubing at approximately 1000' (30 jts) and pulled same. Rig up cementers to squeeze 4 1/2" casing. Squeezed casing with 50 sxs cement. Max. P.S.I. 800#. S.I.P. 400#. Hooked-up to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 300#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD X BAD

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: GL

I did [ ] did not [ X ] observe the plugging.

DATE 9-8-95

INV. NO. 43463 8-14

Dennis J. Hamel  
(agent)

Form CP-2/3