

4-032085

9-6

E-14,615

API Number: 15-153-20,122 - 00-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE SE NE /4 SEC. 07, 01S, 33 W  
3080 feet from S section line  
440 feet from E section line

Operator license# 5552 Lease: Palmer Well # 9W

Operator: Gore Oil Company County: Rawlins

Address: P.O. Box 2747 Well total depth 4220 137.15 feet  
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 290 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 6 Month: September Year: 1995

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: Order 400 sxs 60/40 pozmix - 6% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1995  
CONS  
7-15-95

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:20 A.M., Day: 6, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 290' cwc with 200 sxs. 5 1/2" set at 4219' with 325 sxs. Prod. Perfs at 4089' - 4166'. PBSD 4187'. D.V. Tool at 2975' with 200 sxs. Mixed and pumped down casing 350 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. 0#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 200#. Close in P.S.I. 150#. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED  
DATE OCT 04 1995  
INV. NO. 43646