

12-18 15-153-20011-00-03

4-041554

E-14,615

API number: 15- - 5-1967

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SE /4 SEC. 06, 01 S, 33 W
440 feet from S section line
2200 feet from E section line

Operator license# 5552 Lease Palmer well # 3W

Operator: Gore Oil Company County Rawlins 135.53

Address: P.O. Box 2757 Well total depth 4170 feet
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 190 feet
w/160 sxs.

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: 9:00A.M. Day: 18 Month: December Year: 93

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: 5 1/2" casing set @ 4166' w/525 sxs. cement. Perf. @ 3794' -
4125'. W.L.M. 4150' - T.O.F. @ 2600' - Dakota @ 2150'.
Ordered 450 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:30A.M. Day: 18, Month: December, Year: 93

Actual plugging report: Hooked-up to 8 5/8" S.P. Pumped in 100 sxs.
cement with 100# hulls. Max. 250#. S.I.P. 150#.
Hooked-up to 5 1/2" casing. Pumped in 350 sxs. cement with 400# hulls.
Max. 500#. S.I.P. 450#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [] did not [] observe the plugging.

Dennis L. Hamel

HO.

(agent)

RECEIVED
STATE CORPORATION COMMISS.
JAN 03 1994
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 1-6-94
INV. NO. 39629