

15-153-2002-00-018
6 031454

11-28

(Signature) 11R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1968
SW SW SW SEC. 5, T 1 S, R 33 WXE
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4074

Lease Name Palmer Well # B #2

Operator: Innes Pet. Inc.

County Rawlins 138.28

Name & Address Box 25

Well Total Depth 4255 feet

Phillipsburg, Ks. 67661

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well Input Well ^{XX} SWD Well D&A

Other well as hereinafter indicated Docket # E 15-426

Plugging Contractor Halliburton Services License Number
Oberlin, Ks.

Address

Company to plug at: Hour: Day: 28 Month: 11 Year: 19 90

Plugging proposal received from Rod Innes

(company name) Innes Pet. Inc.

were: 8 5/8 set at 247 w/250 sks. 4 1/2 set at 4255 w/250 sks. Perf

3826 - 30, 2 3/8 cement lined, tubing stuck in 4 1/2. 4 1/2 started to pull w/tubing.

Acidized tubing; Ran 1/2" tool on wireline to 3800. O.K. from Don Butcher.

To sq tubing; 4 1/2 - 8 5/8 as is. Ordered 450 sks 65/35 poz 8% gel. Halliburton Cement Co.

LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All ^{XX} Part None

Operations Completed: Hour: 11:50 AM Day: 28 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Sq 8 5/8w/10 sks cmt 3 bbls. slurry) cement came up out

side of 8 5/8 into cellar. Sq 2 3/8 tubing w/437 sks cement blend to max psi 600 lbs.

Close in psi 150 lbs. Sq 4 1/2 w/3 sks (1 bbl slurry) Blew out head. Will cut off all pipe

in hole and inspect with possibility of welding a plate on each for additional squeezes.

Remarks:

INVOICED

Additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 2-7-91

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 30572

Carl Goodrow

11-28 MAR 07 1991