

8-14

4-032250

15-153-30011-00-01

E-17,400

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1959

C SW SW /4 SEC. 16, 01, 32 W
660 feet from S section line
4620 feet from E section line

Operator license# 3602

Lease: Wilhelm Unit Well # 1

Operator: Philpott Oil & Gas

County: Rawlins 135.53

Address: P.O. Box 450
Atwood, Kansas 67730

Well total depth 4170 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 372 feet
W/300 sxs.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell Kansas 67665

Company to plug at: Hour: P.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Roger Philpott

Company: Philpott Oil & Gas Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00 P.M., Day: 14 Month: August Year: 1997

Actual plugging report: 8 5/8" set at 372' w/300 sxs cwc. 5 1/2" set at 4236' with 250 sxs. Prod. Perf. At 3995' - 4145'. Shot at 2200' - 1600' - 1200'. Recovered 600' of 5 1/2" Squeezed w/90sxs cement blend 300# hulls. Hole full. CIBP at 3547' with cement on plug. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

Form CP-2/3

INVOICED

DATE 9-16-97

INV. NO. 49018

8-14

RECEIVED 9-16-1997

10.