

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20498-00-01
Spot: SESWSW Sec/Twnshp/Rge: 2-1S-27W
330 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: WYATT Well Number: 2-134
County: DECATUR Total Vertical Depth: 3460 feet

Operator License No.: 31660 Conductor Pipe: Size feet:
Op Name: ENERGY SEARCH OPERATING COMPANY Surface Casing: Size feet: 219
Address: P.O. BOX 31697 Production: Size 4.5 feet: 3426 175 SX CMT
AURORA, CO 80041 Liner: Size feet: 112.45

Well Type: EOR UIC Docket No: E25572.1 Date/Time to Plug: 12/22/2000 8:00 AM

Plug Co. License No.: 31660 Plug Co. Name: ENERGY SEARCH OPERATING COMPANY

Proposal Rcvd. from: RAY DORTHY Company: ENERGY SEARCH OPERATING CO Phone: (303) 344-2067

Proposed Plugging Method: Ordered 225 sxs 60/40 posmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/22/2000 11:15 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 219' w/160 sxs cwc. 4 1/2" set at 3426' w/175 sxs.
Squeezed annulus at 1281' w/125 sxs, HDL plus 50 sxs 60/40 pozmix - 2% gel.
PBTD 1205'.
Top squeezed with 125 sxs HDL.
Plugged 4 1/2" with 115 sxs 60/40 pozmix - 10% gel with 200# hulls.
Backside full to surface.
Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION
01-03-2001
JAN 03 2001

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

RECEIVED
DATE 1/3/01
WV. NO. 2001061227

Form CP-2/3

DEC 27 2000

OXFORD EXPLORATION COMPANY
 1030 DENVER CLUB BLDG.
 DENVER, CO. 80202
 CONTR MURFIN DRILLING COMPANY

REPLACEMENT CARD:
 #2-134 WYATT

2-1-27W
 SE SW SW

CTY. DECATUR

GEOL. JAMES L. REEVES FIELD WARNER

E 2535 KB CM 4/23/80 CARD ISSUED 8/21/80 IP P 35 B0 & 4 BWPD
 2530 GL LKC 3219-3306 OA

-	+	-	+
-	+	-	+
-	+	-	+

API 15-039-20,498

LOG	TOPS	DEPTH	DATUM
ANH		1920	+ 615
SEV		3034	- 499
TOP		3056	- 521
DR CR		3123	- 588
OREAD		3163	- 628
LANS		3216	- 681
B KC		3430	- 895
PBTD		3426	- 891
RTD		3460	- 925

8-5/8" 219/160sx, 4 1/2" 3426/175sx

NO DST'S
 CORE (1) 3212-65, FULL REC

MICT - CO, PF (LANS 'A') 5/3219-21,
 SWB DRY/60", PF (LANS 'C') 12/3300-06,
 PF (LANS 'B') 9/3256-60, PF (LANS 'A')
 5/3229-31, SWB DWN, NO FL, SET STR PKR
 3224 & 3210, AC 1500G (15% CRA), SWB
 DWN & REC 1 BF, EST 15% O/30", RESET
 PKRS 3238-3224 TO TST LANS 'A' SD, SWB

INFO RELEASED: 7/29/82 - WAS
 OPERATIONS SUSPENDED
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS