

15-039-200970060

~~15-039-19011-00-00~~

6 031135

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
100' E of  
SW NE, SEC. 18, T 1S, R 26 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4964

Operator: D.C.F. Exp  
Name & Address: 940 Wadsworth Blv.  
Suite 100  
Lakewood, Colorado 80215

3300 feet from S section line  
1880 feet from E section line

Lease Name Huff Well # B-2

County Decatur 116.16

Well Total Depth 3574 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 13 Month: May Year: 19 88

Plugging proposal received from Ronnie

(company name) Kelso (phone)

were: 8 5/8" set at 246' w/200 sks. 5 1/2" set at 3572' w/150 sks. PBSD 3557'.

Perf 3257' - 60'. Order sand and Common Cement. Pull pipe. Order 200 sks Cement Blend and 500# Hulls. Halliburton Cement Co. LaRue Water Trucks

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1988  
9-16-1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30PM Day: 13 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Sand Bottom to 3500' w/5 sks Common Cement on sand w/bailer

5 shots. Recovered 908' of 5 1/2" casing. Squeezed 8 5/8" w/200 sks Cement Blend w/5 sks

Hulls mixed in. Max Psi 500#. Close in Psi 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (operator) observe this plugging.

DATE 9-20-88

INV. NO. 22281

Signed Carl Goodrow (TECHNICIAN)