

DISTRICT CONSERVATION AGENT'S REPORT
15-137-00573-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 61-3

LOCATION SE SE NW

SEC. 31 TWP. 3 RGE. 23

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 9 Lease Mindrup

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3686 Feet.

Plugging Contractor West Supply Co & Globe Cementing

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 261' circulated with cement - 5 1/2" 3684' with 75 sax cement behind.

Filled with sand to 3670', set 4 sax cement with dump bailer, pulled 1500' 5 1/2" to 700', circulated hole with heavy mud (25 sax Gel) through 5 1/2" - displaced 20 sax cement through 5 1/2" at 700', heavy mud to 240', displaced 20 sax cement through 5 1/2" at 240', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Edwin Terry
District Conservation Agent

Date 12-4-57

12-9-57

PLUGGING
FILE SEC 31 T. 3 R. 23a
BOOK PAGE 61 LINE 3