

APR 29 1982
4-29-82
CONSERVATION DIVISION
Wichita, Kansas

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-137-00323-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name John O. Farmer (Mr. Eickman)

Complete Address P.O. Box 352 Russell, Kansas 67665

Lease Name Mindrup Well No. 3

Location C W/2 NW Sec. 31 Twp. 3 Rge. 23 (East) (West)

County Norton Total Depth 3703

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing

Address Russell, Kansas License No. _____

Operation Completed: Hour: 2:00pm Day: 20 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 1/2 @ 280' w/125 sx : 5 1/2 @ 3701 w/75 sx
Cast plug @ 3400 - pumped in 2 hulls, 10 gel,
100 sx (50/50 pozmix 62 gel. 3 3/4 cc), no pressure, wait 3 hrs,
pumped 25 sx cement; pressure to 500# PSI. -
Hook-up to head on head - pump in 15 sx cement & 1 hull;
pressure to 458# PSI.

(Allied
Cementing)

Amount of Surface Casing: 280'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 5-7-82

INV. NO. 116-12