

DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

15-137-00630-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 33-21

LOCATION SW SE NE

SEC. 25 TWP. 3 RGE. 24

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 5 Lease Lawson

Operator H. Gore Address 400 Brown Bldg Wichita,

Field _____ County Norton

Total Depth 3740 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. 1

Address _____

(Describe briefly the manner in which the well was plugged)

3 5/8" at 243' circulated with cement - 5 1/2" at 3712' with
100 sax cement behind.

Filled with sand to 3700', set 4 sax cement with dump bailer,
pulled 1085' 5 1/2", mud to 243', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 7 - 1954

CONSERVATION DIVISION
Wichita, Kansas

Edwin Perry
District Conservation Agent

Date 6-2-54

PLUGGING
FILE SEC 25 T 3 R 24
BOOK PAGE 33 LINE 21

6-7-54