



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Csg. Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Glen N. Rupe,

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Derks Well No. 1

Location: CNW-SE Sec. 4 Twp. 3 Rge. (E)(W) 23

County: Norton Total Depth 3578' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Voth was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated with 185 Sx.  
3577'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back or perforations indicated.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx, cement, staged.

Very truly yours,

*K. L. Nichols*  
Conservation Division Agent