

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-137-30102-00-00

RECEIVED
OCT 8 1966
10-03-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Johnny Jones of Southwest Csg. Pulling Cohas this
date requested permission to plug the following described well:

Bill Hubbell
Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Bill Hubbell,

Complete Address: 706 Union Center, Wichita, Kansas.

Lease Name: Horesky Well No. 1

Location: CNE-NW Sec. 15 Twp. 3 Rge. (E)(W) 23

County Norton Total Depth 3680' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jones was instructed to plug the well as follows:

224'--8 5/8" Surface pipe, cement circulated.

3678'--5 1/2" Production casing cemented with 125 Sx.

Top perforations from 3640' to 3646'

Sand well back to 3620' and set 5 Sx. cement with dump bailer.

Set bridge @ 450' and fill to bottom of cellar with Redi-Mix.

Very truly yours,

M. L. Nichols
Conservation Division Agent