

State of Kansas



15-137-19011-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1966
 09-30-1966
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Johnny Jones of Southwest Casing Pulling has thisdate requested permission to plug the following described well:
Bovaird Supply Co.Mr. Jones guarantees payment of the plugging fee.Operator's full Name: Bovaird Supply Company,Complete Address: Box #897, Great Bend, Kansas.Lease Name: Horesky Well No. 1Location: NW-NE Sec. 15 Twp. 3 Rge. (E)(W) 23County Norton Total Depth 3724 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Jones was instructed to plug the well as follows:211'--8 5/8" Surface pipe, cement circulated.3722'--4 1/2" Production casing cemented with 50 Sx. Open hole completion.

Sand well back to 3700' and set 3 sacks cement with dump bailer. Pull 4 1/2" casing. If fluid down hole to 450' set sand and rock bridge and fill to bottom of cellar with Redi-Mix.

Very truly yours,

W. L. Nichols
 Conservation Division Agent