



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-137-30073-00-00

RECEIVED  
APR 3 1967  
04-08-1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Oil Property Management, Incorporated,

Complete Address: 300 Insurance Building, Wichita, Kansas.

Lease Name: Henderson Well No. B-1

Location: NW-NW-NW Sec. 10 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3548' Knight Csg. Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Voth was instructed to plug the well as follows:

160'--8 5/8" Surface pipe, cement circulated.  
3537'--5 1/2" Production casing cemented with 50 Sx. No perfor-  
ations--open hole completion.

Sand well back to 3530' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 40 sacks gel using 5 Sx.

hulls in initial gel and follow with 75 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent