

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # _____ EXPIRATION DATE _____

OPERATOR Hummon Corporation API NO. 15-137-20,254 00-00

ADDRESS 400 One Main Place COUNTY Norton

Wichita, Kansas 67202 FIELD _____

** CONTACT PERSON _____ PHONE _____ PROD. FORMATION _____

PURCHASER _____ LEASE Persinger

ADDRESS _____ WELL NO. 1

WELL LOCATION NW/4 SE/4 NE

DRILLING Red Tiger Drilling Company 660' Ft. from North Line and

CONTRACTOR 1720 KSB Building 660' Ft. from West Line of

ADDRESS Wichita, Kansas 67202 the NE (Qtr.) SEC 23 TWP 3S RGE 24W.

PLUGGING Red Tiger Drilling Company

CONTRACTOR 1720 KSB Building

ADDRESS Wichita, Kansas 67202

WELL PLAT			

(Office Use Only)

KCC KGS

SWD/REP _____ PLG. _____

TOTAL DEPTH 3,730' PBD _____

SPUD DATE 6/7/82 DATE COMPLETED 6/13/82

ELEV: GR 2,401 DF 2,404 KB 2,406

DRILLED WITH (XXXX) (ROTARY) (XXX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 262' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

Wilber D. Berg, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Wilber D. Berg (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 21st day of June, 1982.

SANDRA L. MENDOZA STATE NOTARY PUBLIC SEDGWICK COUNTY, KANSAS MY APPT. EXP. _____

Sandra L. Mendoza (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 2/13/86

** The person who can be reached by phone regarding any questions concerning this information.

Rec'd 6-23-82

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Hunnon Corporation

LEASE #1 Persinger

SEC. 23 TWP. 3S RGE. 24W

FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
			NAME	DEPTH
Shale	0	615		LOG TOPS
Shale & Sand	615	1215		
Sand & Shale	1215	1880	Heebner	3416 -1010
Shale	1880	1981	Lansing	3458 -1052
Anhydrite	1981	2011	B/KC	3638 -1232
Shale	2011	2626	Gorham Ls	3678 -1272
Shale & Sand	2626	2860	Reagan Sd	Absent
Shale	2860	3213	Gran Wsh	3711 -1305
Lime & Shale	3213	3383	LTD	3730
Shale & Lime	3383	3597		
Lime	3597	3726		
Granite Wash	3726	3730		
RTD				
<p>DST #1: 3696-3711' OP 20/15/15/15 FP 33-33, 33-33 Rec. 2' Mud SIP 33-33 HP 2065-2044</p> <p>DST #2: 3700-3730' OP 30/30/30/30 FP 33-33, 33-33 Rec. 5' Mud SIP 33-33 HP 2066-2044</p>				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	268'	Common	180	2% Gel, 3% C.C.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbis.	Gas MCF
	Water % bbis.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Perforations