

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 208
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23266-0000
LEASE NAME Baier
WELL NUMBER 1-7

RECEIVED
AUG 12 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely and return
to this Div. office within 30 days.

1300 Ft. from West Line of Section
2310 Ft. from North Line of Section

LEASE OPERATOR Mull Drilling Co., Inc. SPOT LOCATION Approximately S/2 S/2 Nw of
ADDRESS P.O. Box 2758 Section 7 Township 22s Range 13w
CITY, STATE, ZIP Wichita, Kansas 67201-2758 County Stafford
PHONE # 316-264-6366 Date Well Completed August 9, 2004
Character of Well Dry and Abandoned Date Plugging Commenced August 9, 2004
Date Plugging Completed August 9, 2004

The plugging proposal was approved on August 8, 2004 at 5:00 pm (date)
by Jim Holland (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3870
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	125	296	8-5/8"	296	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Received plugging orders on 08/08/04. Heavy mud in hole and between all plugs. Bottom plug at 3840'/40 sx, 2nd plug at 850'/50sx, 3rd plug at 350'/50sx and top plug at 40'/15sx cemented to surface. Total of 160sx 60/40 Poz; 6% Gel in hole. Plugged rathole using 15sx same blend, no mousehole. Plugging completed 2:30 am on 08/09/04. Acid Services ticket #8159. SDC reported plugging to KCC on 08/09/04.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Co., Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 10th day of Aug., 2004



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

Bu

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Baier 1-7

LOCATION: Approximately S/2 S/2 Nw of Section 7 T 22s R 13w
API: 15-185-23266-0000 Stafford County, Kansas

OWNER: Mull Drilling Co., Inc.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 02-Aug-04
COMPLETED: 09-Aug-04

TOTAL DEPTH: **DRILLER** 3870 FEET
LOGGER Did not log FEET

Ground Elevation: 1913
KB Elevation: 1922

LOG

0 -	1 FEET	Top Sand
1 -	8 FEET	Clay
8 -	21 FEET	Sand and Gravel
21 -	90 FEET	Sand and Gravel
90 -	185 FEET	Sand and Clay
185 -	805 FEET	Redbeds
805 -	835 FEET	Anhydrite (Driller's)
835 -	1620 FEET	Shales and Salt
1620 -	3840 FEET	Limestone, Shale and Dolomite
3840 -	3870 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 3:15 pm on 08/02/04. Drilled 12-1/4" hole to 296'. Ran 9 joints of used 28# 8-5/8" surface casing, tally 300' set at 296' KB. Cemented with 275 sx Class A, 3% CC, 2% Gel, Cement did circulate. Plug down at 8:30 pm on 08/02/04. Allied Cementing ticket #17315. Welded straps on bottom 3 joints, tacked collars on remaining 6 joints.

Production Casing

Received plugging orders on 08/08/04. Heavy mud in hole and between all plugs. Bottom plug at 3840'/40 sx, 2nd plug at 850'/50sx, 3rd plug at 350'/50sx and top plug at 40'/15sx cemented to surface. Total of 160sx 60/40 Poz; 6% Gel in hole. Plugged rathole using 15sx same blend, no mousehole. Plugging completed 2:30 am on 08/09/04. Acid Services ticket #8159. SDC reported plugging to KCC on 08/09/04.

DEVIATION SURVEYS

3/4	degree(s) at	240	feet
1	degree(s) at	3850	feet