

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

15-015-30262 00-00

Lease Operator: Palomino Petroleum, Inc.  
 Address: 4924 SE 84th St., Newton, Ks. 67114-8827  
 Phone: (316) 799-1000 Operator License #: 30742  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: July 8th, 2004 (Date)  
 by: Wichita District - Doug Louis <sup>KCC</sup> <sup>BEM</sup> (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: N/A Bottom: N/A T.D. 2705'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-N/A  
 Lease Name: Moore "B"  
 Well Number: #6 <sup>N-1</sup> <sup>KCC</sup>  
 Spot Location (QQQQ): NW - NW - SE  
2310 Feet from  North /  South Section Line <sup>BEM</sup>  
2310 Feet from  East /  West Section Line  
 Sec. 36 Twp. 24 S. R. 3E  East  West <sup>8-13-04</sup>  
 County: Butler  
 Date Well Completed: 4/8/1965 3-25-1965  
 Plugging Commenced: July 8th, 2004  
 Plugging Completed: July 14th, 2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	123'	7"	123'	0'
	Production	0'	2701'	4"	2701'	2701'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Tubing was stuck. Pulled 20,000 over sting weight - freed. Pulled out tubing. Made 2 runs with sand pump. Had tubing tested. Ran sand pump 4 times - lots of mud.  
 Ran in mud anchor, seating nipple, 10 jfs., packer and rest of tubing. Ran in 8' & 6', 2-3/8" sub. Tried to circulate 80 bbls. of salt water-it started to come up all around well. Pulled tubing out. Broke production head loose and dug out to casing head-put working head on. Tallied in packer to 305'. Pressured up-held. Went to 456'-held; 610'-held; 762'-held; 1067'-held; 1370-didn't hold. Pulled out packer. Ran in tubing to bottom. Spotted sand on bottom. Pulled tubing. Set C.I.B.P. @ 1000'. Perforated @ 250'-circulated 10 - 20sx. Filled up casing.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc License #: 6901  
 Address: P.O. Box 231, Claflin, Kansas 67525

RECEIVED  
AUG 05 2004  
KCC WICHITA

Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.  
 State of Kansas County, Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

**KAREN J. MITCHELL**  
Notary Public - State of Kansas  
My Appt. Expires 4/13/06

(Signature) Joseph F. Strube  
 (Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 30th day of July, 20 04

Karen J. Mitchell  
Notary Public

My Commission Expires: 4/13/06

GOERING-HEDRICK #6 MOORE 'B' 36-24-3E  
 NW NW SE  
 Contr. EUREKA DRLG BUTLER County

E 1314 KB Comm. 12/28/64 Comp. 4/8/65 II: PMP 25 BOPD + SOME W,  
 (MISS 2692-96 & 2701-05)


SMP Tops	Depth	Datum
LANS	1965	-651
KC	2238	-924
B KC	2400	-1086
MISS DOLD	2683	-1369
TD	2705	-1391

Casing  
 7" 123  
 4" 2701

NO TESTS:

RTD 2703: 4" 2701: CO DP 2705;  
 16/2692-96: A 1000: REC LD: POP:

POTWIN



GEOL: J. R. DANIELS;

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 AUG 05 2004  
 KCC WICHITA