

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-137-20,370 -00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kiwanda Energy, Inc. OPERATORS LICENSE NO. 9121

ADDRESS P. O. Box 1320, Wichita, KS 67201-1320 PHONE # (316) 267-2697

LEASE (FARM) Clark WELL NO. 1 WELL LOCATION W/2 SE SW COUNTY Norton

SEC. 20 TWP. 3S RGE. 24 (~~EXX~~(W) TOTAL DEPTH 3710' PLUG BACK TO

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 249' CEMENTED WITH 175 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Circulate heavy mud in hole. 1st plug at 3655'

20 sx. 2nd plug at 1925'-20 sx. 3rd plug at 1235'-100 sx. 4th plug at 300'-40 sx. 5th plug at

40'-10 sx w/wiper plug. All cement 60/40 pozmix, 6% gel, 1 sx Floccel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? No  
(If not, explain) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 9:30 p.m. on 3-06-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768 4-3-89

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. \_\_\_\_\_

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Warton  
(Operator or Agent)

DATE 3-27-89

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas