

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

15-137-20191-00-00

API Number 15 - - - - - (of this well)  
Lease Owner Baird Oil Company, Inc.  
Address Box 7, Logan, Kansas 67646  
Lease (Farm Name) Dirk Well No. 1  
Well Location 400'W & 400'N NE SE Sec. 4 Twp. 3S Rge. 23 (E)      (W) X  
County Norton Total Depth 3563' Field Name       
Oil Well      Gas Well      Input Well      SWD Well      Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 7:30 p.m. 10-01-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:  
Robert Spencer Address 113 8th Street, Wakeeney, KS  
Plugging Contractor Abercrombie Drilling, Inc. License No.       
Address 801 Union Center, Wichita, Kansas  
Invoice covering assessment for plugging this well should be sent to: 10-14-1980  
Name Baird Oil Company, Inc.  
Address Box 7, Logan, Kansas 67646

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1980  
CONSERVATION DIVISION  
Wichita, Kansas

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent  
Jack L. Partridge, Asst. Secy.-Treas  
Date: 10-08-80

15-137-20191-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Baird Oil Company, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: DIRK #1  
 LOCATION: 400' W & 400' N of NE SE,  
 Sec. 4-3S-23W, Norton County, Kansas  
 SPUD DATE: 09-23-80  
 COMPLETION DATE: 10-01-80

0	1800	Sand & Shale
1800	3348	Shale
3348	3489	Lime & Shale
3489	3554	Shale & Lime
3554	3563	Sand
	3563	Rotary Total Depth

Spud hole @ 4:15 p.m. 09-23-80. Drilled 217' of a 12-1/4" hole. Ran 5 joints of 8-5/8" 20# casing (tally 209.11') Set @ 214' K.B. Cemented with 200 sx. common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 9:00 p.m. 09-23-80.

T.D. 3563' LTD 3560'. Set 1st plug @ 850' with 60 sx., 2nd plug @ 200' with 30 sx., 3rd plug @ 40' solid bridge with 10 sx., rathole with 5 sx., 50/50 posmix, 6% gel. Plug was down @ 7:30 p.m. 10-01-80.

SAMPLE TOPS:

Anhydrite 1845'  
 B/Anhydrite 1878'

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-14-1980  
 OCT 14 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the DIRK #1, 400' W & 400' N of NE SE, Section 4-3S-23W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec.-Treas

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 8th day of October, 1980.

Jeanette A. Metheny  
 Jeanette A. Metheny, Notary Public



State of Kansas



JOHN CARLIN  
R. C. LOUIX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

October 10, 1980

WELL PLUGGING AUTHORITY

15-137-2091-00-00

Dirk #1 <sup>NE</sup>  
App. SE ~~SE~~ SE, Sec. 4-3S-23W  
Norton

3567

*Abercrombie Drilling Inc.*


Baird Oil Company  
Box 7  
Logan, KS

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

  
For Administrator

Mr. Gilbert Balthazor, Box 9, Palco, KS 67657  
is hereby assigned to supervise the plugging of the above named well.