

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-137-00582-00-00

API NUMBER n/a

LEASE NAME Calvin Lawson

WELL NUMBER 3

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 25 TWP. 3s RGE. 24 ~~(E)(X)(W)~~

COUNTY Norton

Date Well Completed 1-54

Plugging Commenced 5-3-91

Plugging Completed 5-3-91

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-30-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? See CP-1

Producing Formation Arbuckle Depth to Top 3724' Bottom 3726' T.D. 3726'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	0	242	8 5/8"	242'	0'
		0	3724	5 1/2"	3724'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate 5 1/2" at 2050' and 1275'. Pump down 5 1/2" 100 sx 65/35, 10% gel w/200# hulls, 40 bbls gel, 175 sx 65/35, 10% gel w/100# hulls. Maximum pressure 750 psi. Pump down 8 5/8"-5 1/2" annulus 100 sx 65/35, 10% gel w/100# hulls. Maximum pressure 400 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

Name of Plugging Contractor B. J. Services License No. _____

Address Hays, KS

MAY 23 1991

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


Scott W Scheurman (Employee of Operator) ~~or Operator~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheurman

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 91



Rebecca K. Crawford
Notary Public

My Commission Expires: 1-7-95