

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00369-00-00
Spot: NESE Sec/Twnshp/Rge: 29-17S-22W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: HAIR Well #: 1
County: NESS Total Vertical Depth: 4388 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING INC DBA LARS
Address: 562 WEST HIGHWAY 4
OLMITZ, KS 67564

CIBP Size: feet: 4100 WITH 4 SX CMT
CIBP Size: feet: 4220
PROD Size: 4.5 feet: 4387
SURF Size: 8.625 feet: 252 WITH 165 SX CMT

\$142⁶¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2004 2:45 PM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: PUMP 300# HULLS & 40 SX CMT. DISPLACE WITH MUD & PRESSURE. PLUG AT 1550' WITH 50 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2004 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4100' WITH 4 SX CMT. SHOT CASING AT 775' & PUMPED 80 SX CMT. DID NOT COME LOOSE. SHOT AT 654', DID NOT COME LOOSE. SHOT AT 537' CAME LOOSE. PULLED CASING TO 300' AND PUMPED 50 SX CMT. PULLED CASING & TOPPED OFF WITH 50 SX CMT. PULLED CASING & TOPPED OFF WITH 50 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4243	4257		
4161	4165		

RECEIVED
AUG 16 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 537' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE

8-17-04

INV. NO.

2005060363

[Handwritten mark]