

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-00584-00-00<sup>03</sup>  
Spot: NWSESW Sec/Twnshp/Rge: 25-27S-8E  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: LEWIS A Well #: 4  
County: GREENWOOD Total Vertical Depth: 2759 feet  
PROD Size: 4.5 feet: 2756

Operator License No.: 5242  
Op Name: PETROLEUM MANAGEMENT, INC.  
Address: 14201 EAST CENTRAL  
WICHITA, KS 67230

# 89<sup>67</sup>

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/16/2004 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: Company: Phone:

Proposed  
Plugging  
Method:

Plugging Proposal Received By: WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/16/2004 5:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

PERFORATED CASING @ 1850' & 500' RAN TUBING TO 2645' MIXED & PUMPED 130  
SXS CEMENT, 5% GEL & 200 PNDs COTTON SEED HULLS, PULLED TUBING TO 1320'  
MIXED & PUMPED 72 SXS CEMENT, PULLED TUBING TO 600' PUMPED 48 SXS  
CEMENT, PULLED ALL TUBING OUT, PUMPED 48 SXS CEMENT TO SURFACE SHUT  
IN WELL WITH 100 PSI. 295 SXS CEMENT TOTAL

RECEIVED  
JUL 02 2004  
KCC WICHITA

RECEIVED  
KCC DISTRICT #3

JUN 17 2004 *mh*

CHANUTE, KS

Remarks:

Plugged through:

District: 03

Signed Mike Heffern  
(TECHNICIAN)

INVOICED  
DATE 7-7-04  
INV. NO. 2005060031