

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22104-00-00
Spot: W2NWSSEW Sec/Twnshp/Rge: 23-20S-12W
660 feet from S Section Line, 1650 feet from W Section Line
Lease Name: KRUEGER Well #: 3
County: BARTON Total Vertical Depth: 3369 feet

Operator License No.: 31647
Op Name: CHURCHHILL, KIM DBA K.C. OPERATI
Address: 534 S E 70 AVE.
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3369 75 SX CMT
SURF Size: 8.625 feet: 231 200 SX CMT

49
\$ 109

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2004 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off casing to 3290' - topped with 5 sxs cement.
Cut casing loose at 1590'.
Pulled up to 1500' - mixed and pumped 100 sxs cement with 400# hulls.
Pulled up to 600' - spotted 40 sxs cement with 100# hulls.
Pulled up to 220' - circulated cement with 50 sxs.
POOH and topped with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3324	3329		

RECEIVED
AUG 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)
INVOICED

DATE 8-17-04

INV. NO. 2005060360

Form CP-2/3

AUG 12 2004

ALPINE DRILLING CO INC
 200 E FIRST #500 WICHITA, KS 67202
 #3 KRUEGER 200'NW,C W/2 SE SW
 CONTR HUSKY DRILLING CO INC CTY BARTON

GEOL JEFF BURK FIELD KRUE

E 1822 KB CM 10/3/80 CARD ISSUED 11/26/80 IP P 30 BOPD, NW
 1817 GL
 API 15-009-22,104 ARB OH 3369-75

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
*ANH		590	+1232
*B/ANH		607	+1215
HEEB		2993	-1171
TOR		3009	-1187
DOUG		3026	-1204
BR LM		3117	-1295
LANS		3139	-1317
BKC		3316	-1494
ARB		3352	-1530
LTD		3369	-1547
RTD		3375	-1553
* SAMPLE TOPS			

8 5/8" 231/200sx; 5 1/2" 3369/75sx
 DST (1) 3258-83(KC)/30-30-30-30, 10'M
 SIP 49-49#, FP 36-36/36-36#
 DST (2) 3349-75(ARB)/30-45-60-45,
 60'GIP, REC 60'OCM, 60'o & GCM,
 60'HO & GCM, 60'MCGSY OIL, SIP
 695-659#, FP 61-58/98-122#
 MICT - CO, (ARB OH), SWB DWN & REC
 300'FL (7'RO), AC 500 G (15%), SWB
 1/2 BOPH, NOFU 600' o, NW, SWB 1.67
 BOPH, NW/ 5HRS, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 NOV 26 1980