

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20763-00-00
Spot: SWNENW Sec/Twnshp/Rge: 35-14S-19W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HERL Well #: 4
County: ELLIS Total Vertical Depth: 3762 feet

Operator License No.: 31933
Op Name: M E KLEIN & ASSOCIATES, INC
Address: PO BOX 721436
NORMAN, OK 73070

PROD Size: 5.5 feet: 3658 100 SX CMT
SURF Size: 8.625 feet: 1375 600 SX CMT

27
\$ 122

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2004 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DICK SCHEMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2004 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3500' - topped with 5 sxs cement.
Cut casing loose at 2790'.
Pulled up to 2000' - mixed and pumped 100 sxs cement with 300# hulls.
Pulled up to 1375' - spotted 40 sxs cement with 100# hulls.
Pulled up to 675' - spotted 40 sxs cement with 100# hulls.
Pulled up to 250' - circulated cement with 85 sxs cement.
POOH. Topped with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3599	3612		
3559	3566		

RECEIVED
AUG 17 2004
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 8-17-04

Form CP-2/3

INV. NO. 2005060368

AUG 13 2004

BEACON RESOURCES
 WICHITA, KANSAS
 CONTR DRILLING & SONS

#4 HERL
 CTY ELLIS

35-14-19W
 SW NE NW

GEOL JAY DIRKS FIELD ANTONINO SOUTH

E 2111 KB CM 9/17/71 ^{CARD} ISSUED 12/2/71 IP P 25 BOPD N/W
 LKC 3599-66 &
 3602-12

LOG	TOPS	DEPTH	DATUM	
				8 5/8" 1375/600sx; 5 1/2" 3658/100sx
ANHY	1368	+ 743		DST(1) 3548-70(LANS)/30-30-30-30, 105' GIP, 15'SOCM & 60' HOCM (35% OIL), BHP 305-305#/30", FP 31-52#
HEEB	3376	-1265		
TOR	3398	-1287		
LANS	3423	-1312		DST(2) 3568-90(LANS)/60", 65'WM, BHP 348-337#/30", FP 52-52#
CONG	3732	-1621		
ARB	3752	-1641		DST(3) 3599-3617(LANS)/60", 12'WM, BHP 52-116#/30", FP 31-31#
RTD	3761	-1650		
LTD	3762	-1651		
				MICT, PF(LANS) 40/3602-12, 250GALS MA, WOULDN'T TREAT, PF(LANS) 28/3559-66, 250 GALS MA, MP 1000# TP 600# ON VAC/ 10", SWB LD SWB 1 BF/3RD HR, 80% OIL, 1500 GALS (28%) AC & 2000 GALS (15%) AC, REC LD, SWB 8 1/2 BOPH/6HRS, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS