

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15065-20153-00-00

LEASE NAME Schamberger

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3194 Ftt. from S Section Line

4726 Ftt. from E Section Line

SEC. 25 TWP. 8 RGE. 25 ~~W~~ or (W)

COUNTY Graham

Date Well (Completed) 7-9-1968 <sup>KCC</sup> <sup>WEN</sup> <sup>8/17/04</sup>

Plugging Commenced 7/22/04

Plugging Completed 7/22/04

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St. Suite 500 Denver, Co.

PHONE # (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 22, 2004 (date)

by Roger Moses (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation LKC Depth to Top 3918 Bottom 3923 T.D. 3990

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content        | From | To   | Size   | Put In | Pulled out |
|-----------|----------------|------|------|--------|--------|------------|
|           | Surface Casing | 0    | 214  | 8 5/8" |        | None       |
|           | Producing Csg  | 0    | 3989 | 4 1/2" |        | None.      |
|           |                |      |      |        |        |            |
|           |                |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Perforated the 4 1/2" casing at 2200' and at 1300'. Pumped 50 sacks of 60/40 POS w/10% Gel and 50#'s of hulls down the 8 5/8" casing at 100 pounds pressure. Pumped 300 pounds of hulls and 150 sacks of cement down 4 1/2" casing followed with 150#'s of hulls mixed into 50 sacks of cement at 900#'s pressure, ISIP 600#'s

Name of Plugging Contractor Allied Cement Company <sup>KCC</sup> <sup>WEN</sup> <sup>8/17/04</sup>  
Encore Operating Company License No. 99996  
33069

Address 1601 Blake St. Suite 500 Denver, CO

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company <sup>AUG 16 2004</sup>

STATE OF Colorado COUNTY OF Denver , s.s. <sup>KCC WICHITA</sup>


Roland Nyp

(Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STREET, KANSAS

June R Nyp  
Notary Public



My Commission Expires: 9-30-04