

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-21340-00-00

LEASE NAME Hefner-Coberly

WELL NUMBER 1

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 26 TWP. 14 RGE. 28 (E) or (W)

COUNTY Gove

Date Well (Completed) 9-20-1990

Plugging Commenced 7/13/04

Plugging Completed 7/13/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St Suite 500 Denver, Co.

PHONE# (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 13, 2004 (date)

by Darrel Dipman (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Marmaton Depth to Top 3922 Bottom 3928 T.D. 4300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	0	227	8 5/8"		None
	Producing Csg	0	4295	4 1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set: GIRP @ 3900' Ran 2" tubing to 3870', spotted 50 sacks of 60/40 Pos w/10% Gel cement @ 3870'. Pulled the tubing to 2000' and pumped 115 sacks of cement down the tubing and circulated the cement to surface. Pulled the tubing and topped off the 4 1/2" casing with 10 sacks of cement. Pressured the 8 5/8" casing to 400#'s pressure. Did not pump cement.

Name of Plugging Contractor Plains Inc. License No. 4072

Address Ness City, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company


STATE OF Colorado COUNTY OF Denver, s.s.

Roland Nyp

(Employee of Operator or ~~KCC~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS



AND SWORN TO before me this 10th day of Aug, 2004

Irene R Nyp
Notary Public

My Commission Expires: 9-30-04