

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
September 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.  
Address: 3101 N. Rock Rd. Suite 125, Wichita, KS.67226  
Phone: (316) 636-5155 Operator License #: 31389  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3258'

API Number: 15-159-01829-00-00  
Lease Name: J.A Williams  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - NW  
330 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 13 Twp. 18 S. R. 8  East  West  
County: Rice kcc  
Date Well Completed: 2-6-1939 8-17-04  
Plugging Commenced: 8-9-04  
Plugging Completed: 8-9-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10"	208'	None
				7"	3151'	None
				5-1/2"	147'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3050' and 7 sacks cement. Perforated well @900' and 260'.  
Welded 5-1/2" to 7", welded 7" to 10-3/4", welded 5-1/2" nipple to surface. Ran in 900' of  
of 2-3/8" tubing, pumped 50 sacks cement, pulled up to 750', pumped 400# hulls, pulled

up to 260' and circulated 70 sacks cement to surface. Pulled rest of tubing and topped  
off w/20 sxs. cement. Pumped 35 sxs. down 10-3/4", Tied onto 7" and pressured up. Plugging Complete  
Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of August, 20 04

Irene Herzberg My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 17 2004

KCC WICHITA

*bn*