

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-039-20749-00-00

LEASE NAME Guy R. Streyer

WELL NUMBER 1

SPOT LOCATION NE, SE, NW

SEC. 12 TWP. 3S RGE. 26 (E) or (W)

COUNTY Decatur

Date Well Completed 2-15-85

Plugging Commenced 2-15-85

Plugging Completed 2-15-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Diamond Shamrock Exploration Company

ADDRESS P.O. Box 400, Amarillo, Texas 79188-0001

PHONE # (806) 378/3851 OPERATORS LICENSE NO. 9123

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #6 1014 Cosy, Hays, KS 913-628-1200

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing-Kansas City Depth to top 3525 bottom 3637 T.D. 3950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From	To	Size	Put in	Pulled out
	Red Bed	0	326	8 5/8	326	0
			3926	4 1/2	3926	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from 3926 feet to 4 feet each set. Rig up Howco. Plugged well in accordance with KCC as follows: Pump 200sx 50/50 Poz w/6% gell & 3% cc cmt down 4 1/2" csg. After 6bbls of cmt was pumped 2sx of cotton seed hulls were mixed in w/the cmt. After 30 add'nal bbls of cmt were pumped the 4 1/2" csg loaded. After 50 more bbls the pump was released f/the cmtg head & another 4 1/2bbls of cmt was pumped into the 4 1/2" csg. Shut cementing head in. Rigged up to cmt surface csg. Attempted to pump into surface csg. Surface csg pressure up to 700#-couldn't (If additional description is necessary, use BACK of this form.) (see back)

Name of Plugging Contractor Murfin Drilling License No. 6033

Address 250 North Water, Wichita, KS 67202 316/267-3241

STATE OF Texas COUNTY OF Potter, ss.

Jay Voorhis (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jay Voorhis

(Address) P.O. Box 400, Amarillo, Tx 79188-0001

SUBSCRIBED AND SWORN TO before me this 7 day of March, 1985

Patti Jones  
Notary Public

My Commission expires: 5-06-85

RECEIVED  
STATE CORPORATION COMMISSION  
3-11-85  
MAR 11 1985  
CONSERVATION DIVISION  
Wichita, Kansas