

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-039-20,857 <sup>00-00</sup>

LEASE NAME Hix

WELL NUMBER 1

3630 Ft. from S Section Line

<sup>2970</sup>  
~~3630~~ 2970 Ft. from E Section Line

SEC. 8 TWP. 3S RGE. 26 ~~XXXX~~ (W)

COUNTY Decatur

Date Well Completed 10-28-89

Plugging Commenced 10-28-89

Plugging Completed 10-29-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Eagle Creek Corporation

ADDRESS 107 N. Market, Suite 509, Wichita, KS 67202

PHONE# (316) 264-8044 OPERATORS LICENSE NO. 30129

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-29-89 (date)

by State Plugger, Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	281.25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Circulate heavy mud in hole. 1st plug from 2125' to 2025' w/25 sx. 2nd plug from 1300' to 900' w/100 sx. & 1 sack hulls, 3rd plug from 325' to 165' w/40 sx. 4th plug from 40' to surface w/10 sx., with wiper plug. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle Creek Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or CONSERVATOR of CONSERVATION DIVISION of Wichita, Kansas


above-described well, being first duly sworn on oath, says: That I have knowledge of Wichita, Kansas statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 89

Sharan J. Branstetter Notary Public  
My Commission Expires: May 18, 1993



RECEIVED  
STATE CORPORATION COMMISSION

NOV - 6 1989  
11-6-89  
CONSERVATION DIVISION  
Wichita, Kansas