

3 055782

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-003-~~NA~~ 19278-00-00
NWNWSE Sec/Twp/Rge 07-21-21E
2145 feet from south section line
2295 feet from east section line

#3500

TECHNICIAN'S PLUGGING REPORT

Operator License # 5820

Lease/Well# MULKEY 18

County ANDERSON

Operator: KENT DRLG

Well Total Depth 655 feet

Name & 1406 E 4TH AVE

Production Pipe: 2 Size Feet 607

Address GARNETT, KS 66032

Surface Casing: 10 3/4 Size Feet 13

AB oil well XXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: PART OF THE BUSH CITY SHOE STRING

Plugging Contractor: R J ENTERPRISES Lic. # 3728

Address: 1203 4TH AVE GARNETT KS 66032

Company to plug at: Hour: 12:00 Day: _____ 3 Month: 8 2004

Plugging proposal received from: ROGER KENT

Company Name: R J ENTERPRISES Phone: 785-448-6995

Were: _____

607' OF 2" PIPE SET ON RAG PACKER WITH 18 SX CEMENT

PUMP 2" FULL WITH CEMENT

RUN 250' OF 1" PIPE OUTSIDE 2" PIPE FILL TO SURFACE WITH CEMENT

Plugging Proposal Received by: T J WELSH

Plugging attended by Agent: All XXXX Part _____ TECHNICIAN
None _____

Operations Completed: Hour: 12:30 Day: _____ 4 Month: 8 2004

Actual Plugging Report: _____

RAN 525' OF 3/4" PIPE INSIDE 2" PIPE

RAN 210' OF 1" PIPE OUTSIDE 2" PIPE

PUMP 102 SX CEMENT INSIDE 2" PIPE CEMENT CAME UP INSIDE AND OUTSIDE 2" PIPE

PULL 1" AND 3/4" PIPE---- ON 8-4-04 TAG CEMENT INSIDE 2" AT 60' OUTSIDE 2" AT 100'

PUMP 2 SX CEMENT INSIDE 2" AND 28 SX CEMENT OUTSIDE 2"

CEMENT AT SURFACE

Remarks: _____

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Thomas J Welsh
TECHNICIAN

RECEIVED
AUG 09 2004
KCC WICHITA

INVOICED
DATE 8-18-04
INV. NO. 2005060373

DW