

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22501-00-00
Spot: NWSESW Sec/Twnshp/Rge: 30-25S-5E
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MURRAY Well #: 6
County: BUTLER Total Vertical Depth: 3217 feet

Operator License No.: 5044
Op Name: WHITE PINE PETROLEUM CORPORATI
Address: 110 S. MAIN ST., SUITE 500
WICHITA, KS 67202

PROD Size: 5.5 feet: 2695 175 SX CMT
SURF Size: 8.625 feet: 264 100 SX CMT

\$ 104⁵⁵

Well Type: SWD UIC Docket No: D23126.0 Date/Time to Plug: 05/24/2004 12:00 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: WILBUR C. BRADLEY Company: BRADEN PETROLEUM & WELL PL Phone: (316) 262-5429

Proposed Plugging Method: SAND BACK TO 2645, DUMP 6 SX CMT ON TOP OF SAND, WORK PIPE TO RECOVER APPROXIMATELY 1200', RUN IN TO 315 SET TOP PLUG. RUN TUBING IN TO TOP OF PLUG AND PUMP CEMENT TO SURFACE. PULL TUBING, FILL CELLAR. AS PER KCC RULES AND REGULATIONS.

**RECEIVED
KCC DISTRICT #2
AUG 5 - 2004**

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE **WICHITA, KS**
Date/Time Plugging Completed: 06/01/2004 12:00 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Perfs:

Sanded to 2645' and dumped 6 sacks of cement on top of sand. Worked pipe to recover approximately 1200'. Ran in to 315' and set top plug. Ran tubing in to top of plug and pumped cement to surface. Pulled tubing and filled cellar.

114 sacks
60/40 posmix with 4% gel

RECEIVED
AUG 06 2004
KCC WICHITA

Remarks: BRADEN #4-406 (5/24/2004) & #4-409 (6/1/2004)

Plugged through: TBG

District: 02

Signed: *Bill Johnson*
(TECHNICIAN)

INVOICED

DATE 8-9-04

WELL NO. 2005060331