

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20293-00-02
Spot: SESW Sec/Twnshp/Rge: 17-29S-2E
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FARBER Well #: 4
County: SEDGWICK Total Vertical Depth: 2380 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

CIBP Size: feet: 2380
PROD Size: 5.5 feet: 3503 60 SX CMT
SURF Size: 8.625 feet: 156 100 SX CMT

\$77³⁵

Well Type: SWD UIC Docket No: D25428.0 Date/Time to Plug: 03/19/2004 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: BEAR PETROLEUM, INC. Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: DUMP SAND FROM 2380' TO 2190', DUMP BAIL 5 SX CMT ON SAND, SHOOT AND PULL 5-1/2" CASING RUN PIPE INTO 206', CIRCULATE TO SURFACE, PULL PIPE AND TOP OFF WELL. AS PER KCC RULES AND REGULATIONS. DV TOOL AT 2411", 60 SX STALNAKER.

RECEIVED
KCC DISTRICT #2

AUG 6 - 2004

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE
Date/Time Plugging Completed: 04/13/2004 5:00 PM KCC Agent: DAVE WERTZ

WICHITA, KS

Actual Plugging Report:

SAND BACK FROM 2380'-2190'. DUMP BAIL 5 SX CMT ON SAND., SHOT PIPE OFF @ 1845' & PULLED, RAN TBG TO 200', CIRC. CMT TO SURF. PULL TBG, TOPPED WELL OFF W/CMT, 60/40 POZ, 4% GEL.

Perfs:

Top	Bot	Thru	Comments
2240	2264		

RECEIVED
AUG 06 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed David Wertz
(TECHNICIAN)

INVOICED

DATE 8-9-04

INV. NO. 2005060330