

3022618

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-26847-00-00  
Spot: SWSESESE Sec/Twnshp/Rge: 5-24S-16E  
170 feet from S Section Line, 470 feet from E Section Line  
Lease Name: NEWBY Well #: 12  
County: WOODSON Total Vertical Depth: 1068 feet

Operator License No.: 4085  
Op Name: KING, TOM DBA KING ENERGY CO.  
Address: 2 TIMBER DRIVE  
IOLA, KS 66749

SURF Size: 8.625 feet: 40

#36

Well Type: OH DH UIC Docket No: Date/Time to Plug: 07/22/2004 10:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: TOM KING Company: KING ENERGY CO. Phone: (620) 365-7750

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 6.25" HOLE TO 1068'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 1068', A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/22/2004 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN TO 1068'. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO 1068'. THE DRILL PIPE WAS PULLED TO 700' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 250' CEMENT WAS PUMPED INTO THE DRILL UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
AUG 09 2004  
KCC WICHITA

RECEIVED  
KCC DISTRICT #3

AUG 4 2004 C.P.T.  
CHANUTE, KS

Remarks:

Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-9-04

INV. NO. 2005060334