

RECEIVED
MAY 20 2004
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22,654-0002 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 9431 E. Central, Suite 100 CITY Wichita

STATE KS. ZIP CODE 67206-2345 CONTACT PHONE # (316) 684-8481

LEASE RADER "B" WELL# 1-18 SEC. 18 T. 21S R. 11 (East/West)

C - SW - NE - SW SPOT LOCATION/QQQQ COUNTY Stafford

1650 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

3630 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 273' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3618' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3493'-3507'

ELEVATION 1821'KB T.D. 3630' PBDT 3510' ANHYDRITE DEPTH 581'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, hulls, cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (620) 793-0915 / (620) 786-5783 (Cell)

ADDRESS P.O. Box 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925
(company name) (contractor's)

ADDRESS 401 West Main, Lyson, KS. 67554 PHONE # (620) 727-3410

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT
DATE: 05/17/2004 AUTHORIZED OPERATOR/AGENT: Loveness Manje
(signature)

6/04

8/04

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- RADER "B" 1-18
Located: SW NE SW, Section 18-21S-11W, Stafford County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 26, 1990

COMPLETED: March 4, 1990

TOTAL DEPTH: 3630'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 220 Sand and Clay Stringer	Ran 6 joints 8 5/8" casing. 261.20'
220 - 275 Red Bed	pipe set at 273 K.B. Cemented with
275 - 635 Red Bed and Shale	225 sacks 60/40 Pozmix, 2% gel and
635 - 1350 Shale	3% cc. Plug down at 11:00 AM,
1350 - 3630 Lime and Shale	2-26-90, by Howco.
	Ran 86 joints 5 1/2", 15.5# casing.
	3609.95' pipe set at 3618' K.B.
	Cemented with 400# salt flush and
	500 gal. super flush, 50 sacks Lite
	and 125 sacks F. G. Holl mix. Plug
	down at 2:15 PM, 3-4-90, by Howco.

Deviation Surveys: 1 1/4° at 3295'
1° at 3630'

RECEIVED

MAY 20 2004

KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

May 25, 2004

Re: RADER B #1-18
API 15-185-22654-00-02
SWNESW 18-21S-11W, 1650 FSL 3630 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor