

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION

JAN 06 1977
1-6-77
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-039-20376-0-00 (of this well)
Lease Owner DuPont Oil Co.
Address 660 Edgewater Road, Wichita, Kansas
Lease (Farm Name) ARNOLD Well No. 1
Well Location SW NE NE Sec. 9 Twp. 3S Rge. (E) 26 (W)
County Decatur Total Depth 3728' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 12:00 noon 1-02-77

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 S. 2nd St. Hill City, Ks.

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name DuPont Oil Co.

Address 660 Edgewater Road, Wichita, Kansas

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Jack L. Partridge, Asst. Sec.-Treas.
Date: January 5, 1977

CONTRACTOR'S WELL LOG

OPERATOR: DuPont Oil Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: ARNOLD #1
 LOCATION: SW NE NE, Section 9-3S-26W
 Decatur County, Kansas
 SPUD DATE: 12-23-76
 COMPLETION DATE: 1-02-77

0	150	Clay & Sand
150	200	Sand
200	1144	Shale
1144	1233	Sand
1233	1590	Shale & Sand
1590	1800	Shale
1800	1935	Sand
1935	2149	Shale
2149	2184	Anhydrite
2184	2322	Shale
2322	3036	Shale & Lime
3036	3290	Lime & Shale
3290	3435	Shale & Lime
3435	3541	Lime & Shale
3541	3690	Lime
3690	3728	Shale & Lime
	3728	Rotary Total Depth

Spud hole at 8:45 p.m. 12-23-76. Drilled 275' of 12 1/4" Hole. Ran 262.62' of used 8 5/8" surface casing - 28#. Welded all collars. Set surface casing at 272.62'. Cemented with 180 sx. of common cement, 2% gel, 3% Ca. Cl. Sun Cement. Plug was down at 1:00 a.m. 12-24-76. Cement did circulate. Will drill out from under surface at 3:00 p.m. 12-26-76.

T. D. 3728', Set 1st plug at 1150' with 70 sx., 2nd plug at 250' with 20 sx., 3rd plug at 40' with 10 sx. Job complete at 12:00 noon 1-02-77.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 06 1977

1-6-77

CONSERVATION DIVISION
 Wichita, Kansas

SAMPLE TOPS:

Anhydrite 2149' (+446)
 B/Anhydrite 2184' (+411)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the ARNOLD #1, SW NE NE, Section 9-3S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of January, 1977.



Kathy S. Goertz
 Kathy S. Goertz, Notary Public 3

State of Kansas



15-039-20376-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 6, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Arnold
Description	SW NE NE Sec. 9-3-26W
County	Decatur
Total Depth	3728
Plugging Contractor	Abercrombie Drilling Co., Inc.


DuPont Oil Company
660 Edgewater Road
Wichita, Kansas 67230

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.