

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-039-20,857-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Eagle Creek Corporation OPERATOR'S LICENSE NO. 30129

ADDRESS 107 N. Market, Suite 509, Wichita, KS 67202 PHONE # (316) 264-8044

LEASE (FARM) Hix WELL NO. 1 WELL LOCATION NE SE NW COUNTY Decatur

SEC. 8 TWP. 3S RGE. 26 (~~EXXX~~(W) TOTAL DEPTH 3750' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 281.25' CEMENTED WITH 180 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2125'-25 sx. 2nd plug at 1300'-100 sx. & 1 sack hulls. 3rd plug at 325'-40 sx. 4th plug at 40'-10 sx., with wiper plug, Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 3% cc.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 11:00 p.m. on 10-28-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: **RECEIVED**
STATE CORPORATION COMMISSION

Wayne Shively PHONE # (913) 743-6308

ADDRESS 229 S. 11th, Wakeeney, KS 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: November 2, 1989