

State of Kansas



15-137-00708-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1974

CONSERVATION DIVISION
Wichita, Kansas

11-4-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kans.

Lease Name: Lawson Well No. 8

Location: CEL-SE/4 Sec. 36 Twp. 3 Rge. (E)(W) 24

County: Norton Total Depth 3793 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

263'--8 5/8" Surface casing, cement circulated with 135 Sx.
3783'--5 1/2" Production casing cemented on bottom with 100 Sx. (Open hole completion).

Sand well back to 3770', set 5 Sx. cement with dump bailer, Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 130 Cu. Ft. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent