

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Lawson Well No. 7

Location: CSE/4 Sec. 36 Twp. 3 Rge. (E)(W) 24

County: Norton Total Depth 3782' Oil Well

Gas Well Input Well ^{KCCG} SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

260'--~~8 1/2~~ 10 3/4" Surface casing, cement circulated with 135 Sx.
3781'--7" OD Production casing cemented on bottom with 100 Sx. (Open hole completion).

Sand well back to 3750' and set 6 Sx. cement with dump bailer. Pull

7" casing and squeeze well with 5 sacks hulls, 43 sacks gel and 190

Cu. Ft. cement, staged.

Very truly yours,

K. L. Dickels
Conservation Division Agent